

PGPUB-DOCUMENT-NUMBER: 20020198755

PGPUB-FILING-TYPE: new

DOCUMENT-IDENTIFIER: US 20020198755 A1

TITLE: Integrated quality assurance control system  
to manage  
construction projects

PUBLICATION-DATE: December 26, 2002

INVENTOR-INFORMATION:

NAME	CITY	STATE	
Birkner, Charles Christian	Magnolia	TX	US
EIDahdah, Elias George	Houston	TX	US
Martinez, David Frederick	Cypress	TX	US

APPL-NO: 09/887907

DATE FILED: June 22, 2001

INT-CL-PUBLISHED: [07] G06F017/60

INT-CL-CURRENT:

TYPE	IPC	DATE
CIPP	G06Q10/00	20060101

US-CL-PUBLISHED: 705/8, 705/7

US-CL-CURRENT: 705/8, 705/7

REFERENCE-FIGURES: 2

ABSTRACT:

A construction management system includes a handheld computer adapted to collect construction data from the field; a planning system to track budgetary information; a design system to perform site engineering assessment; and a construction system to track material consumption and progress for each project, the construction system adapted to receive data collected from the handheld computer, store daily project reports and generate key indicator

reports.

## BRIEF SUMMARY:

### BACKGROUND OF THE INVENTION

[0001] The present invention generally relates to a quality assurance control system to manage construction projects.

[0002] In many large-scale construction projects, a developer needs to provide construction bid specification preparation, which is evaluated before the developer is awarded a contract. Once the developer receives the contract, various construction management and contract administration practices need to be implemented. These practices include developing a plan that will allow the effective coordination of operations, construction, and engineering personnel. The plan in turn specifies procedures for field inspection, supervision, and testing. The need for project planning becomes even more important for governmental projects and is usually mandated by law for an incorporated political unit or municipality or community.

[0003] Traditionally, project managers have been using spreadsheets, databases, and other software tools for years in order to track the information they need to run their jobs. Much of that information is originally accumulated in file folders and manual logs. A significantly large amount of information is created and used during a life-cycle of a construction project (i.e., from a planning stage through design and construction stages to facility management).

[0004] Various computer systems (e.g., CAD system, analytical system, analytical system, simulation system, etc.) have been developed and introduced by construction firms. However, many of these systems are effective only within certain narrow application domains so that transmission of

information  
between different domains is realized by linking together the  
applications.

[0005] To illustrate, in order to accomplish such a construction project, each person in charge shares the project data with others, and keeps such data for his own use, and based on his allotted share of the work. However, the project activities are interrelated with each other in a complex manner so that it is very difficult for the persons in charge to have information in common with each other. Such complexity is because the project data is stored, retrieved, computed and updated as the project progresses from the viewpoint of each person in charge with respect to each particular piece of information.

[0006] Although computerized spreadsheets and databases offered significant productivity gains in modeling complex data, none was as intuitive to use as the old, but familiar paper and pencil. To use the new technology, the user had to type information into the cells of the spreadsheet. In the hand of inexperienced users, the data entry aspect was unpleasant. Further, the verification for correct data entry was time consuming. Additionally, the user had to master many complex and arbitrary operations. Furthermore, conventional computerized spreadsheets and databases still required users to manually enter the information.

[0007] Recently, portable computing appliances such as those offered by Palm Computing, Inc. offer the ability to capture data on the spot. However, portable computing appliances must balance the conflicting requirements of the readability of the displayed characters and the size of their display screens. On one hand, the portability requirement implied that the screen be small. On the other hand, the readability requirement pushed in the opposite

direction  
and dictated that the display area be as large as possible. However,  
as  
computing appliances with large screens consumed more power, were  
more fragile,  
expensive and bulkier, most portable computers offered only a small  
display  
surface. The selection of a small display size restricted the user  
into making  
undesirable choices between displaying either larger characters or  
more  
information.

#### SUMMARY

[0008] A construction management system includes a handheld computer adapted to  
collect construction data from the field; a planning system to track  
budgetary  
information; a design system to perform site engineering assessment;  
and a  
construction system to track material consumption and progress for  
each  
project, the construction system adapted to receive data collected  
from the  
handheld computer, store daily project reports and generate key  
indicator  
reports.

[0009] Implementations of the system may include one or more of the  
following.  
The handheld computer collects work in progress data such as project  
and  
contract identification, inspector identification, item number,  
location, and  
one or more description of activities. The the handheld computer  
collects  
labor related information such as labor type, quantity and hours.  
The handheld  
computer also collects equipment information such as equipment type,  
quantity,  
hours in use and stand-by hours. The handheld computer can also  
collect  
submittal information such as weather condition, comments, and an  
inspector  
name. The handheld computer sends collected information to a server.  
The  
collected information may be sent wirelessly using a wireless  
handheld unit.  
Alternatively, a modem coupled to the handheld computer can be used

to transmit  
the information. Also, a hot-sync cradle coupleable to the handheld  
computer  
can be used for hot-syncing the collected information for  
transmission to a  
server.

[0010] Advantages of the system may include one or more of the  
following. The  
system provides comprehensive program and construction management  
services  
supporting teams of engineers, construction managers, schedulers,  
cost control  
engineers, estimators, and document control specialists to oversee  
the  
planning, design and construction of large-scale transportation and  
public work  
projects.

[0011] The system facilitates teamwork between the staff of the  
owner, designer  
and contractors of a project. During the initial development phase  
of a  
project, the system expedites the selection of a design team and the  
development of a realistic, and achievable, budget and schedule.  
During this  
phase the system also assists in defining the design criteria for the  
project  
to meet the expectations of the owner.

[0012] In the Design Development Phase, the system facilitates and  
manages  
quality control/quality assurance for the project. At critical  
phases during  
design phase, the system supports updating of the project schedule  
and budget  
in relation to the level of design. The purpose of these updates is  
to  
maintain the original project scope or to identify, in a timely  
manner the  
necessity of revisions to the plan. The system also conducts  
constructability  
reviews throughout the design process. The system also documents all  
aspects  
of a project. Within a given organization, all projects may be  
consistently  
documented. In short, the notebook process provides a standardized,  
easy to  
use, project development process.

[0013] The system manages the construction of multiple projects using inexpensive handheld computers communicating with a server. The handheld computer stores daily field journals such as work progress of unit bid items and contract deliverables, manpower utilization, equipment utilization, and general information including weather, temperature, remarks, and the inspector's name. The handheld computer also captures an inspection checklist and generates Punch list items, tracks Punch list items, takes facility inventory, and tracks facility repairs and cost estimates. The handheld also handles project documentation, such as project specifications, industry specifications, and drawing logs, among others.

[0014] The system is an integrated program management system where the processes for planning process, designing and constructing operations share the same information. The system can also perform program management where a large construction program can have a plurality of projects within that program. The system can manage the process of planning long range budget plans and after the plans have been approved, the system can specify for a particular year the projects that are in a design phase where an architect or engineering firm performs initial site feasibility studies, performs the design work so that the project can receive bids from construction companies. The system can also provide project tracking on a day to day basis. The tracking can be done using an inspection system field notebook system that tracks the progress of the project on a day to day basis as well as values that are paid to the contractor so that correct intermediate progress payments can be made for a particular project.

[0015] The system is as easy to use as the pen and paper approach and provides information integration advantages, including the ability to capture data from

scanners, barcode readers, or the Internet. Furthermore, as portable computers are typically deployed in field applications by service providers where employees are scattered over a wide geographic area, the information advantages arising from integrating data collected from handheld computers include an ability to link information generated at the client's site with follow-up discussions and letters necessary to close the transaction enhances the efficiency of field personnel. The handheld computer is small and inexpensive. Thus, field personnel can perform data collection without carrying a relatively bulky laptop or notebook computer.

[0016] Other advantages of the invention may include one or more of the following. The system provides an efficient, integrated system for keeping track of job details that are constantly changing. The management of proposal submittals becomes convenient. Further, the tracking submittal responses or approvals is streamlined. The submittals, transmittals, change orders, request for information, meeting minutes, daily reports, activity logs, and other job related documents are organized and instantly searchable. The system enables information related to a building production to be managed unitarily by making use of a computer and to properly transmit production information generated at each stage of the production to the next process. The field-based project managers can be constantly in touch with the main office via phone, fax, or courier to ensure that their job information is accurate and up-to-date. Production and cost information from the system can be sent directly to the accounting staff for entry into the job costing and accounting software. Further, the system avoids requiring duplicate entries to be made.

DRAWING DESCRIPTION:

## BRIEF DESCRIPTION OF THE DRAWINGS

[0017] FIG. 1 is a diagram illustrating an integrated construction project management system.

[0018] FIG. 2 is a diagram illustrating a networked computer system for handling an integrated construction management system.

[0019] FIG. 3 is a diagram illustrating major modules associated with an integrated construction management system.

[0020] FIG. 4 is a diagram illustrating a system for handling information updates from field personnel.

[0021] FIG. 5 is a diagram illustrating a planning-design-construction process flow.

[0022] FIG. 6 is a diagram illustrating processing of a capital improvement plan.

[0023] FIGS. 7a-7c are flowcharts illustrating two design phases.

[0024] FIG. 8 is a diagram illustrating one sequence of processing data in an integrated construction management system.

[0025] FIG. 9 is a diagram of an exemplary handheld computer to collect field data.

[0026] FIG. 10 is a flowchart illustrating operations performed on the handheld computer of FIG. 9.

[0027] FIGS. 11-18 are exemplary user interfaces on the handheld computer in collecting data in the field.

[0028] FIG. 19 shows an exemplary process 600 to handle quality assurance checking for one or more construction projects.



[0029] FIGS. 20-25 show exemplary user interfaces for the process of FIG. 19.

#### DETAILED DESCRIPTION:

##### DESCRIPTION

[0030] Referring now to FIG. 1, a project control system for providing program management of capital improvement projects is shown. The system 100 consists of a plurality of modules, a planning system 102, a design system 104, and a construction system 106. The project control system can handle multiple projects in their planning phases, design phases and construction phases. The planning system 102 is a budgetary system that tracks finding sources, the allocation of the funding sources, and scheduling information. The planning system 102 also maintains data relating to preliminary site feasibility studies such as estimates of the cost of the project.

[0031] The design system 104 allows the user to perform detailed site assessments. The user can check for a variety of concerns, for example environmental concerns. The design system 104 also allows the user to start a preliminary design that meets predefined requirements on a particular project. The design system 104 also performs contract management aspects of the design contract, including tracking whether a design engineering company or an architectural firm has delivered certain items. The design system 104 also performs contract management and archives any court document control such as correspondence between an owner and a design firm.

[0032] The construction system 106 tracks the actual materials consumed and the progress of the project. For example, data relating to construction items previously bid upon can be reviewed in determining the quantity of material

delivered and the payment to a particular contractor for its construction items. The system 106 can track on a daily basis the quantities of the materials being delivered to the job site, the progress of the work and the resulting pay estimate sheets. The construction system 106 also performs various contract management functions, including archiving all contract documents and correspondence associated with a particular construction management construction firm.

[0033] In combination, the planning system 102, the design system 104 and the construction system 106 allow an organization with multiple projects to see an overall project schedule so that any level of details can be reviewed in each one of these phases.

[0034] FIG. 2 illustrates an exemplary hardware configuration system 110 for executing the modules of FIG. 1. In the system of FIG. 2, one or more handheld computers 112, 114 and 116 are carried by one or more inspectors. The handheld computers 112, 114 and 116 are connected to a dialup network 120. The data transfers can be performed using this dial-up network or directly from local area network at the main office. Specifically, the dialup network can simply be the Plain Old Telephone Service (POTS) network.

[0035] The dialup network 120 in turn is connected to a server 130 which is protected by a firewall. The firewall is a security system (hardware and/or software) that isolates resources of a computer system or network from objects outside of the system or network. Generally, the firewall allows for inside objects to request and receive connections to outside objects (e.g. for inside applications to access outside Internet sites, among others), but prevents outside applications from accessing resources inside the system or network.

[0036] Some firewalls permit only email traffic through them, thereby protecting the network against any attacks other than attacks against the Email service. Other firewalls provide less strict protections, and block services that are known to be problems. Generally, firewalls are configured to protect against unauthenticated interactive logins from the "outside" world. This, more than anything, helps prevent vandals from logging into machines on the user's network. More elaborate firewalls block traffic from the outside to the inside, but permit users on the inside to communicate freely with the outside.

[0037] The server 130 is connected to one or more contract databases 132, 134, 136, and 138. The server 130 also is connected to a master server 140. The master server 140 is connected to one or more master databases 142, 144, and 146. The master server 140 is also connected to one or more workstations, including a project manager workstation 150, a project engineering workstation 152, and an estimator workstation 154.

[0038] In this implementation, the master server 140 can be a plurality of redundant, fail-over servers, where each server can provide resources independent of the other until one of the servers fails. Each server continuously monitors the other server. In one implementation, server processes available from Microsoft Corp. of Redmond, Wash. called Microsoft Cluster Server (MSCS) uses a hot-standby technique in which a primary server and a standby server send "keep alive" messages back and forth so that the standby server is activated if it cannot contact the primary server. When one of the servers fails, the surviving server acquires the shared drives and volumes of the failed server and mounts the volumes contained on the shared drives. Applications that use the shared drives can also be started on the surviving server after the failover. Further, a manual-failover

operation can be performed on the shared volumes at any time in order to perform tasks such as scheduled maintenance on one of the servers. As soon as the failed server is booted up and the communication between servers indicates that the server is ready to own its shared drives, the servers automatically start the recovery process.

[0039] The databases 142-146 can reside on one or more network RAID data storage devices. In such an embodiment, the network RAID data storage device is a collection of disks under hardware or software control so that a single drive failure does not bring the system of FIG. 1 down. The data storage devices may be a RAID-1 system, in which every disk has a mirror image of its data stored on another disk. Alternatively, the data storage devices may be a RAID-2 or RAID-3 sub-system which stripes user data across a group of drives (typically four or eight drives per group). The data storage devices may also be a RAID-4 or RAID-5 sub-system which stripes block (or sometimes groups of blocks) of data and stores the data entirely on an individual disk.

[0040] Referring now to FIG. 3, major modules associated with the system of FIG. 2 is shown. In FIG. 3, a field journal 162 is maintained on an inspector handheld computer 164. The inspector handheld computer 164 communicates with a firewall server 166. The firewall server 166 in turn communicates with a main server 170.

[0041] A plurality of modules are in turn are executed on the main server 170. The modules include a new project module 171, a project information module 172, a new contract module 173, a closure module 174 and a search module 175. The new project module 171 creates and initializes database structures for a new

project. The project information module 172 provides management and accounting reports associated with a particular project. The new contract module 173 creates and initializes database structures for a new contract. The search module 175 searches for information relating a particular project or contract. The closure module 174 generates various final inspection reports and authorization for final payments. Additionally, the main server 170 executes a key indicator status (KIS) summary status module 176 that tracks the projects in terms of overall dollars and schedule time and provides at a quick glance whether each project is ahead of schedule or over/under budget.

[0042] Various reporting modules are also executed on a server 170. These modules include, but are not limited to, a daily report module 167, a monthly report module 168, and an estimate report module 169. Additionally, a change order module 177 performs the document management involved in sending out requests for information and eventually the change orders on a contract.

[0043] Referring now to FIG. 4, processes executed on the handheld computer 164 of FIG. 3 are shown. In FIG. 4, a plurality of inspector handheld computers 182, 184, and 186 communicate with a telephone company terminal 188. The terminal 188 can communicate over the POTS network. The terminal 188 is connected to one or more modems 190, 192, and 194. The modems 192 and 194 in turn transfer information to a dialup server 200 which contains a project database. The dialup server 200 communicates with a database administrator workstation 202, which allows a database administrator to maintain and operate the various databases. The dialup server 200 also communicates through a network connection to a main project server 210 which contains a planning design and construction project database. The server 210 also contains an

archival database for all closed projects. The main project server 210 also communicates with a project manager workstation 212 and an engineering/estimator workstation 214. The main project server 210 also communicates with a web site administrator workstation 216 which allows an administrator to manage the web site. The main project server 210 also communicates through the network connection to a web server 220. The web server 220 contains one or more project specific web sites so that the sites can be publicly accessed using the Internet. The web server 220 and the project-specific web site can host the reports generated from the Integrated Construction Project Management System (ICPMS) by saving to a specific folder related to each individual project. The project specific web site can be secured so that only people associated with the project can see reports from the web site.

[0044] The daily projects database contains folders with database files associated with a particular project. After initializing the construction database and performing a new project set up, a resident engineer or a field inspector posts daily reports or daily field journals which track on a daily basis the progress of the work. Each day, the inspector downloads a subset of the master database from the contract database that would only include the project information related to the projects being reviewed that day. At the end of the day, each inspector updates information for his reviewed project(s) and uploads or transmits that information back to the daily project folders in the contract database.

[0045] A field inspector can select the projects that he or she is interested in uploading and downloading. The uploading/downloading processes populate databases on the firewall server. A project estimator initially sets

up a project folder. If a new project is uploaded to a folder on the firewall server network, a unique project folder is created on the dialup server with the following naming convention: a file folder name that correlates to the project number and an assigned contract number and uploads project data into the project folder. If the project already exists, the system simply copies the project data into a new project folder on the server network.

[0046] Subsequently, the inspector sets up a dialup connection, logs-in with the appropriate authorization, and invokes an upload/download menu. The inspector selects a new project that's on the list and downloads information associated with the selected project to his laptop or handheld computer. The information includes data on costs, schedules, bid items, and change orders, among others. Once downloaded, the inspector can update the bid item quantities delivered and field progress information for the project. At the end of the day, the inspector runs a daily field report--daily field journal which includes information on the work performed for that day. The report can also cover a range of days, so that if the inspector has been out on a job all week and has been filling out daily field journals every day, a range of days can be selected for transmission once.

[0047] After the firewall server has been updated, the estimator can repopulate the master database to make it current. The estimator connects to this firewall server and selects one or more projects to refresh the master database. The updating the master database is done with a SQL command which keys off of the project number and the contract as the primary keys.

[0048] Pseudo-code for the synchronization of project information between the inspector's computer and the server is as follows:

[0049] Steps done by the Estimator/DB Administrator

[0050] Enters New Project Information into the Master Database

[0051] Activates the Upload/Download Menu

[0052] Selects the New Project just created

[0053] Selects the Send Button

[0054] This Creates a unique project folder on the Dial Up Server with the following naming convention: Project #+Contract #. This populates this folder with a database file containing only that projects information. The project is ready for the inspector to Hot Sync to his or her laptop or alternatively to his or her handheld computer. Pseudo code for steps done by the Inspector for a laptop hotsync is as follows:

[0055] Activate the Dial-Up Network Connection to the Fire Wall Server

[0056] Activates the Upload/Download Menu

[0057] Select the New Project from a pull down list

[0058] Select the Receive Button to hot sync the laptop computer

[0059] This downloads the project specific database created by the estimator. The inspector creates is Daily Field Journal for that day

[0060] Activates the Upload/Download Menu

[0061] Select the Project from a pull down list and the day or range of days for the field journals to upload

[0062] Select the Send Button

[0063] This uploads only the information that change for that day or range of days selected to the Dial-Up Server

[0064] This completes the hot sync process by the inspector using a laptop computer.



[0065] If the inspector uses Pseudo code for steps done by the Inspector for a laptop hotsync is as follows:

[0066] Activate landline or wireless modem connection to a firewall server

[0067] Use the hot sync process to download project specific data based on an assigned project to the inspector handheld computer

[0068] The inspector or technician completes daily field journal forms or inspector testing form

[0069] Repeat until all project data has been processed

[0070] Steps done by the Estimator/DB Administrator are discussed in the next pseudo-code:

[0071] The Estimator now updates the master database with the current project information

[0072] Activates the Upload/Download Menu

[0073] Selects a Project or Multiple Projects for that day or range of days to update the master database

[0074] Selects the Receive Button to hot sync the master database

[0075] Once the daily project folders have been updated, an administrator of the database takes each project and uploads the folders to the master database that includes information for all the projects. Once data has been collected, a variety of reports can be generated, including a periodic report such as a monthly report, a progress report, a payment report, an estimate report relating to various aspects of contractor payments. Thus, project managers and administrators can have timely access to information for all projects. Old projects are moved to an archive projects database, which stores static data

that is not actively accessed. Data stored in the archive can be imported back into the database for review if needed.

[0076] FIG. 5 shows a planning/design/construction process. First, a new project is started (step 402). Next, various user privileges are assigned (step 404) and planning data is entered (step 406) into a planning projects database 408. The information stored in the project database can be used to generate a capital improvement plan (step 410) and can be exported into a web-accessible format (step 412) and placed on a project-specific web site (step 414).

[0077] Additionally, the information stored on the planning project database can be exported (step 420) as a project information to a design projects database 426. The design projects database can receive contract information (step 422) as well as design information (step 424). The design project database can generate a design status report (step 428) which can be exported to the web format (step 412) for placement on the project specific website (step 414). Additionally, information from the design project database can be provided to a schedule data interface (step 430) that provides output compatible to one or more project schedulers such as Microsoft Project, among others (step 432). Further, the output from the design project database can be provided to a bid package information module (step 434), which in turn can be used in a spreadsheet for contractors to submit cost values on the contract bid items (step 436). This data can be imported (step 438) and analyzed (step 440) and provided to a winning bid export file (step 442). The winning bid output can then be provided to a master construction projects database 450. The master construction projects database can also directly receive project information from the design projects database (step 448).

[0078] The master construction projects database 450 can receive contract data (step 452), project data (step 454), and can also send and receive information (step 456) from a daily activity database 460. The daily activity database 460 handles field project information (step 462) as well as daily field journal information (step 464). The output of the master construction database 450 can also be archived as an archive project information module (step 47-) in a closed projects database 480.

[0079] Referring now to FIG. 6, the planning system 102 is shown in more detail. The planning system 102 manages the long term planning for program management of budgets, funding, and schedules. This long term planning information is the core information used in municipalities and agencies Capital Improvement Plans (CIPs). The planning system 102 includes a module for handling capital improvement plan 232 that can be used to provide decision support for municipalities. For example, a owner or agency can have a five-year capital improvement plan. The owner or agency can categorize different elements in that plan. For example, one may be involved with the parks and recreation program, one may be involved with the fire program, and one may be involved with the street and bridge program.

[0080] The capital improvement plan module 232 communicates with a plurality of program modules 234, 238, and 242. Further, the program module 234 stores information 236 associated with the first project. Similarly, the program module 238 stores information 240 associated with the second project, and module 242 stores information 244 associated with the Nth project. This structure allows for summary roll-up reports at the project, program, and CIP level.

[0081] The planning system 102 includes a Fund/Source Module that maintains multi-year budget plans for the overall CIP process. This allows program managers to create a multi-year Capital Improvement Plans and track the funding sources by program, fund, and by source. Each CIP plan is controlled separately to maintain a historical record of the previous year's CIP plan. This Planning System controls and manages the data associated with this process.

[0082] The Design System manages the document control process for design process. This system contains various modules that provide the PCS functions from Design Contract Award to Construction Contract Award. The following are the modules and the sections below will describe how each Design System module controls the design information by performing documentation control of design information for each individual their projects:

[0083] Design Contract Award Phase Module

[0084] Design Phase I Module

[0085] Design Phase II Module

[0086] Design Review Module

[0087] Post Advertisement to Bid Phase Module

[0088] Post Bid to Construction Contract Award Module

[0089] Phase I spans the time where a user has awarded a contract to a particular design or architectural firm to preliminarily design the project. Phase II spans the time required to perform a complete design where construction details are defined. For instance, if the user is building a building, the Phase I design includes performing a site layout. Phase II Design would be what the user wants an atrium area to look like inside, for example. Phase II would also then specify all the structural

details, for  
example the cabinets and the doors, and the result of Phase II a very  
detailed  
design specification.

[0090] The software is customizable to the individual user by  
developing  
templates that resemble a client's existing forms. These modules are  
all  
follow the software design architecture and allow the user to select  
a forms  
from a dialog box list. This launches the appropriate input window  
to appear  
so the user can view and update the design information as required.

[0091] Referring now to FIGS. 7a, 7b and 7c, operations associated  
with the  
design module 104 is shown. In FIG. 7a, a meeting is initiated (step  
250).  
Next, interim progress reviews are periodically performed, for  
example, every  
two to three weeks (step 250). Next, conflicts between the private  
utility and  
various governmental agencies are coordinated (step 254). In step  
256, various  
investigations are performed. This investigations include  
geotechnical  
investigations, environmental assessments, survey activities and  
archeological  
investigations. Next, the process of FIG. 7a analyzes the real  
estate  
activities associated with the design. These activities include  
railroad right  
of way and private pipeline permits (step 256). Next, a preliminary  
engineering report is drafted (step 260). A schematic design is  
submitted  
(step 262). A pretechnical review is performed (step 264-266). The  
decisions  
and action items of the technical review are captured (step 268), and  
a  
preliminary engineering report is finalized (step 270).

[0092] From step 270, a schematic design is generated and submitted  
for the  
architectural project (step 278). Next, another pretechnical review  
meeting is  
held (step 280-282). The records of the decisions and action items  
associated  
with a technical review committee meeting are stored (step 284). A  
preliminary

engineering report is then generated (step 286). The design development submittal is then sent (step 288). The scope of the final design is refined (step 290). Finally, the project receives a notice to proceed (step 292) before the phase one of the design is deemed to be completed (step 294).

[0093] Phase I Design Module manages the documentation associated with the following fifteen (15) phases of this process. The flowchart on the following page illustrates the Phase I Design process.

[0094] 1. Kick-Off Meeting

[0095] a. Estimate for Payment

[0096] b. Design Consultant Memorandum--Action Item Completion

[0097] 2. Interim Progress Review Meetings

[0098] a. Design Consultant Memorandum--Action Item Completion

[0099] 3. Private Utility and Other Agency Conflict Resolution

[0100] a. Documents in this phase are generated by Design Consultant (DC) this phase is mainly to resolve any private utilities conflicts which could be potential construction conflicts

[0101] 4. Geotechnical Investigation

[0102] a. Authorization to Initiate Geotechnical Investigation

[0103] b. Geotechnical Report

[0104] 5. Environmental Site Assessment

[0105] a. Authorization to Initiate Phase I Environmental Site Assessment

[0106] b. Phase IA ESA Report

[0107] 6. Survey Activities

[0108] a. Authorization to Initiate Survey Work

- [0109] 7. Real Estate Activities
  - [0110] a. Authorization to Initiate Real Estate Activities
  - [0111] b. Real Estate Information Package
- [0112] 8. Archeological Investigation
  - [0113] a. Document reference location information only
- [0114] 9. Other Additional Services
  - [0115] a. Authorization to Initiate Additional Service
- [0116] 10. Preliminary Engineering Report (Draft)
  - [0117] a. Document reference location information only
- [0118] 11. Pre-Technical Review Committee (TRC) Meeting
  - [0119] a. Document reference location information only
- [0120] 12. Technical Review Committee (TRC) Meeting
  - [0121] a. Technical Review Committee Meeting Announcement
  - [0122] b. Technical Review Committee Meeting Agenda
  - [0123] c. Technical Review Committee Meeting Project Summary
  - [0124] d. Record of Decisions and Action Items from TRC Meeting
- [0125] 13. Preliminary Engineering Report (Final)
  - [0126] a. Document reference location information only
- [0127] 14. Contract Amendment or Supplemental Appropriation
  - [0128] a. Professional Scope of Service/Fee
  - [0129] b. If changes accepted than appropriate steps need to be followed for Authorization
- [0130] c. Package, Contract and Ordinance, and Award and Execution of Design Consultant Contract
- [0131] 15. Notice to Proceed (NTP) for Phase II Design

[0132] Referring now to FIG. 7c, Phase II of the design process is shown.  
First, a meeting is kicked off (step 270). Next, interim submittals are generated (step 274). The interim progress review meetings are held to review the interim submittals (step 276). Next, various investigations are performed (step 278). These investigations include geotechnical investigations, environmental site assessments, server activities, railroad activities and/or archeological investigations.

[0133] From step 278, additional operations are performed (step 280). The final design submittal is generated (step 282) and finalized contract documents are generated (step 284) before the Phase II design is completed (step 286).

[0134] Phase II Design module manages the documentation associated with the following eleven (11) phases of this process. The flowchart on the following page illustrates the Phase II Design process.

[0135] 1. Kick-Off Meeting

[0136] a. Record of Decision and Action Items (RDAI)--Action Item Completion

[0137] 2. Interim Progress Review Meetings

[0138] a. Record of Decision and Action Items (RDAI)--Action Item Completion

[0139] 3. Interim Milestone Submittals

[0140] a. Document reference location information only

[0141] 4. Private Utility and Other Agency Conflict Resolution

[0142] a. Design Consultant Internal Activities

[0143] 5. Additional Geotechnical Investigation

[0144] a. Authorization to Initiate Additional Geotechnical Investigation



[0145] 6. Phase II Environmental Site Assessment (ESA)

[0146] a. Authorization to Initiate Phase II Environmental Site Assessment

[0147] 7. Survey Activities

[0148] a. Authorization to Initiate Survey Activities

[0149] 8. Real Estate Activities

[0150] a. Authorization to Initiate Real Estate Activities

[0151] 9. Additional Archeological Investigation

[0152] a. Authorization to initiate Additional Archeological Investigation

[0153] 10. Other Additional Services

[0154] a. Authorization to Initiate Other Additional Services

[0155] 11. Final Design Documents p2 a. Construction Drawings, Completed  
Project Manual, Estimate of Construction Cost, Geotechnical Report, Final  
Engineering Design Report, Completeness Checklist

[0156] Phase II Design Review Module manages the documentation associated with the following eleven (11) phases of this process. The flowchart on the following page illustrates the Final Design Review process.

[0157] 1. Contract Project Director (CPD) Plan Review

[0158] a. Document reference location information only--DC submits final design plans to CPD and PM staff

[0159] 2. Owning Division/User Agency Review

[0160] a. No Documentation

[0161] 3. Constructability Review

[0162] a. No Documentation

[0163] 4. Front-End Documents

[0164] a. Form 00010--Project Information Form (C)

[0165] b. Document 00800--Supplementary Conditions guide (C)

[0166] c. Division 00--Bid Documents--refer to attached page of all bid documents that need to be submitted

[0167] d. Division 01--General Requirements

[0168] e. The purpose of this phase is to develop a package which will consist of Bid Documents, General Requirements, and basic correspondence for the Project Manger to review

[0169] 5. Bid-Ready Documents

[0170] a. No documentation--documents from previous step are reviewed once more and after review the front-end documents are placed into construction documents

[0171] 6. Code Enforcement Review for Building Permit (if required)

[0172] a. Commercial Building Permit Application

[0173] 7. Private Utility Signatures and Other Agency Approvals (if required)

[0174] a. No documentation

[0175] 8. Authorizing Signatures

[0176] a. No documentation--purpose is for all bid-ready documents for project to be approved by owner or agency

[0177] 9. Request for Advertisement

[0178] a. Advertisement for Bids

[0179] b. Request for Advertisement

[0180] 10. Production of Bid-Ready Documents

[0181] a. Plan Holder's List

[0182] 11. Advertisement for Bids

[0183] a. No documentation--purpose is to advertise in the newspaper for bids

[0184] Referring now to FIG. 8, various modules associated with the construction system 106 are shown. First, the help module 108 is provided. Next, a new project launch 110 receives new projects being opened. The new project module is the first module that needs to have user input before any other module will function. This module will consist of the project information table. The new project will have an input field for project name and project number. The project number is critical since the database will key off this number to link other related data tables. Other input fields that will be needed for this module are funding number, funding source, drawing number, key map number, area, and council district. The primary data table that the new project table will be interfacing with is the contract information data table.

[0185] The new project module 110 communicates with a new contract module 112. The new contract module will define the contract information for the project. The module will consist of a contract information data table, contractor information data table, contractor affidavit data table. This module will receive project data from the new project information table. The new contract module will have an input field for the contractor number and contractor name, which will be the primary fields. The contract information will also consist of the unit bid contract, which will define the unit price for each item needed for the project along with its planned quantity. The other input fields will consist of contractor id, contract date, contract amount, contract days, ordinance number, gfs number, contractor name, and contract start date.

[0186] The new contracts module 112 in turn communicates with a bid price

module 114. The Unit Price Bid Contract Module imports the winning construction contractor bid tabulation information. This Bid Tab will be used in by inspectors to track the actual quantities delivered and computation of the contractors earned value will be performed.

[0187] The unit bid price module 114 communicates with a daily field report module 118. This is an output module that will create the daily posting report. This module will be linked and take input from the three data tables described in the Field Journal Module. The major items that will be queried from the data tables and presented in the daily posting report are the item number, location of where the work is being done, description of the type of work, the actual quantity of that item used for that day, a cumulative total of the quantity used for that month including that day, the total quantity used for the entire project including that day, the percentage complete and unit price. The formula required to calculate the cumulative total of quantity utilized for the month is shown in equation 1. and the calculation used to determine the total quantity used for the project is shown in equation 2. Equation 3 shows the formula needed to calculate the percentage work complete.

$Quantity\_Actual = Quantity \text{ of Item per day (Equation 1)}$

$Cumul\_QTY = .SIGMA.(Quantity\_Actual's) \text{ (Equation 2)}$

$\% \text{ Work Compete} = (Plan\_QTY - Cumul\_QTY) / Plan\_QTY \text{ (Equation 3)}$

[0188] A print function will be needed in this module to print out the daily posting report in MS Word format in which the necessary data will be inputted into a defined template.

[0189] In addition, a daily field journal 116 communicates with the daily field reports module 118. This module will consist of four data tables, which are

the daily work progress table, daily equipment table, daily labor force table and submittal table. The user-input fields for the daily work progress table will include the project number, contract number, report date, item number, and actual quantity. The input fields for the daily equipment table will consist of equipment quantity, hours in use, standby hours, site location, and work type. The input fields for the labor will contain manpower, hours and work type. The submittal table will consist of the submitters' names and the weather for that day. All four data tables will be linked using the project number and contract number. This module can be run as a standalone module by the inspector's laptop to connect to a dial-up server. Once the dial-up server connection is established, the send/receive menu allows for uploads and downloads of selected projects.

[0190] The daily field reports module 118 can communicate with a monthly estimate report module 122. This module is also an output module that will basically combined the totals from the daily field reports for each month at the project cutoff date and print a report. The report will consist of each item for the project along with its unit, planned quantity for the entire project, quantity used for the month and quantity used for the entire project through the cutoff date. These items will queried from the daily field report tables monthly. The report will also contain the unit price, total amount spent for each item and cumulative total for all items. The unit price information is defined in the new contract information table and this table will be linked to that table using the contract and project number. The equation to determine the total amount spent on each item to date and cumulative totals are depicted in equation 4 and 5 respectively.

Item Total Amount to Date=.SIGMA.(Quantity\_Actual)\*Unit Price

(Equation 4)

Item Cumulative Totals=Cumul\_QTY\*Unit Price (Equation 5)

[0191] A print function will be needed in this module to print out the daily posting report in MS Word format in which the necessary data will be inputted into a defined template.

[0192] The monthly estimate report module 122 in turn communicates with a document closure module 130. This module function is to develop all the closure documents that are required for project completion. Individual templates will be created for each document. The appropriate tables for each document will be queried to fill out each template. The templates will be created in MS Word format. The closure document templates that will need to be created are listed below.

[0193] Final Payment Certificate

[0194] Change Orders

[0195] Consent of Surety Letter from Contractor

[0196] Contractors Certificate of Final Completion

[0197] Copy of Approved Council Motion

[0198] Affidavit of Work Performed

[0199] Each user of the software package will have their own user-defined documents or forms. These documents are user configurable by updating or adding new templates can be created using MS Word depending on the company's requirements without requiring a software source code change.

[0200] The daily field reports modules 118 can communicate with a change order module 120 in the event changes are required. If so, the change order module 120 communicates with the unit bit price 114 and the new contract module 112.

The requirements for this module are to allow changes to be made to the initial contract. The module will be linked to the new contract table and allow the user to make a change to the original contract. A change order has to go through certain before it is approved. This module will generate the proper documents needed for the change order such as the request for information (RFI), request for proposal (RFP), and the actual change order document. The change order tables will be linked by contract number to extract the appropriate contract information needed for the forms. The change order table will also need to be linked to previous change order (CO) tables to allow the user to know what previous changes have been made to the contract. The fields that will be inputted into the change order tables are the amount and duration of the current change order along with the date that the change order is submitted. This module will then calculate the total amounts of the previous change orders based on equation 6 and previous time extensions based on equation 8. Further, the module will also calculate the revised contract price and revised schedule using equations 7 and 9.

$APCO = .SIGMA.(Previous\ Contract\ Change\ Orders)$  (Equation 6)

$Revised\ Contract\ Price = Original\ Contract\ Price + APCO + Current\ CO\ Amount$   
(Equation 7)

$PTE = .SIGMA.(Previous\ Time\ Extensions)$  (Equation 8)

$Revised\ Schedule = Original\ Contract\ Duration + PTE + Current\ CO\ Extension$   
(Equation 9)

[0201] In addition, a search module 109 is provided to assist users in locating documents when necessary.

[0202] The main function of this module is to determine the project status based on the project's key indicators. This module is for output

there will be  
no inputs. This module will be linked to the project information  
table,  
contract information table, and the estimate tables for each project.  
This  
module will query the latest information from these tables to  
determine if the  
project is ahead of time, on time, or behind. This will be done by  
looking at the  
percentage of work completed against actual days used to complete the  
work  
using equation 10.

% WKComp=.SIGMA.(Item Cumulative Totals)/Revised Contract Price\*100  
(Equation  
10)

[0203] This module will create an summary output table which will  
include the  
project name, gfs number, contract name, contract number, contractor,  
contract  
date, contract amount, contract days, work complete, number of days  
used,  
amount paid, percent of total amount paid (equation 11), and lagging  
indicator  
(Equation 12).

% By Time=Days Used/Revised Schedule\*100 (Equation 11)

% Lagging=% WKComp-% By Time (Equation 12)

[0204] The main function of this Schedule Module module is to track  
the  
schedule for each bid tabulation item. The user interface controls  
the start  
and finish dates for each item. This module provides an interface to  
MS  
Project.TM. that automatically launches, transmits the item  
description, start  
date, and finish date to display the project schedule.

[0205] The main function of this Send/Receive Data Module module is  
to control  
the Daily Field Journal data from the Master Database. This module  
allows the  
inspectors using Inspect-IT and the estimators using Construct-IT to  
manage  
these Daily Field Journal Updates. Before activating the  
Send/Receive Data  
Module, the user will need to dial-up or connect to the project



database  
server. The user selects the project and the date for which these updates are to be performed, and select the appropriate Send or Receive button for the transition required.

[0206] The main function of this module is to control user access and update privileges to the content of the Master Database. This module assumes four (4) user types: Inspector, Estimator, Project Manager, and Database Administrator. In addition, this module allows the Database Administrator to configure the users privileges based on a project by project and department by department basis. In general, the Database Administrator would configure the system to allow the following privileges:

[0207] Inspector: Daily Field Journal (Read/Write)

[0208] Estimator: Daily Field Journal (Read)+Monthly Estimate Report Module (Read/Write)

[0209] Project Manager: Main Modules (Read/Write/Update)

[0210] Database Administrator: (Full Control)

[0211] There will be a help button in the main window. The help will give a complete overview of how the program works and how all the modules are interrelated. Moreover, the help will consist of descriptions of the different functions of the software package. The help will also give a description of each button and its purpose. In addition to the help button that appears in the main window, help on the individual modules will be available. The help on the individual modules will describe the input fields for each module along with the function and use of the module.

[0212] A search function will allow the user to search for a particular item in the database. The search will consist of selecting a project or

contract and  
then searching for a particular item associated with that particular  
contract  
or project. The search will have to be linked to both the project  
and contract  
tables through their project number and contract number to allow the  
user to  
find a particular data item in the database.

[0213] FIG. 9 illustrates an exemplary handheld computer system for  
collecting  
and managing construction data. The computer system is preferably  
housed in a  
small, rectangular handheld enclosure. Referring now to FIG. 9, a  
general  
purpose architecture for entering information into the data  
management by  
writing or speaking to the computer system is illustrated. In FIG.  
9, a  
processor 20 or central processing unit (CPU) provides the processing  
capability for the sketching system of the present invention. The  
processor 20  
can be a reduced instruction set computer (RISC) processor or a  
complex  
instruction set computer (CISC) processor. Preferably, the processor  
20 is a  
low power CPU such as the MC68328V DragonBall device available from  
Motorola  
Inc.

[0214] The processor 20 is connected to a read-only-memory (ROM) 21  
for  
receiving executable instructions as well as certain predefined data  
and  
variables. The processor 20 is also connected to a random access  
memory (RAM)  
22 for storing various run-time variables and data arrays, among  
others. The  
RAM 22 is sufficient to store user application programs and data. In  
this  
instance, the RAM 22 can be provided with a back-up battery to  
prevent the loss  
of data even when the computer system is turned off. However, it is  
generally  
desirable to have some type of long term storage such as a  
commercially  
available miniature hard disk drive, or non-volatile memory such as a  
programmable ROM such as an electrically erasable programmable ROM, a  
flash ROM  
memory in addition to the ROM 21 for data back-up purposes. The RAM

22 stores

a database of the spreadsheet of the present invention, among others.

[0215] The computer system 10 of the present invention has built-in applications stored in the ROM 21 or downloadable to the RAM 22 which include, among others, an appointment book to keep track of meetings and to-do lists, a phone book to store phone numbers and other contact information, a notepad for simple word processing applications, a world time clock which shows time around the world and city locations on a map, a database for storing user specific data, a stopwatch with an alarm clock and a countdown timer, a calculator for basic computations and financial computations, and a database for storing collected construction data. Additionally, project planning tools, and CAD/CAM systems, Internet browsers, among others, may be added to increase the functionality of handheld computing appliances. Users benefit from the software, as the software allow users to be more productive when they travel as well as when they are in their offices.

[0216] The computer system of the present invention receives instructions from the user using one or more switches such as push-button switches in a keypad

24. The processor 20 is also connected to a real-time clock/timer 25 which tracks time. The clock/timer 25 can be a dedicated integrated circuit for tracking the real-time clock data, or alternatively, the clock/timer 25 can be a software clock where time is tracked based on the clock signal clocking the processor 20. In the event that the clock/timer 25 is software-based, it is preferred that the software clock/timer be interrupt driven to minimize the CPU loading. However, even an interrupt-driven software clock/timer 25 requires certain CPU overhead in tracking time. Thus, the real-time clock/timer integrated circuit 25 is preferable where high processing performance is

needed.

[0217] Additionally, the expansion bus 26 can receive a wireless transceiver 31, which is connected to an antenna 32. The wireless communication device 31 satisfies the need to access electronic mail, paging, mode/facsimile, remote access to home computers and the Internet. One simple form of wireless communication device 31 is an analog cellular telephone link where the user simply accesses a cellular channel similar to the making of a regular voice call. However, the transmission of digital data over an analog cellular telephone network can give rise to data corruption. Digital wireless networks such as cellular digital packet data (CDPD) can be used. CDPD provides data services on a non-interfering basis with existing analog cellular telephone services. In addition to CDPD, a communication service called Personal Communication Services (PCS) allows wireless access into the public service telephone network.

[0218] The two-way communication device 31 can also be a two-way pager where the user can receive as well as transmit messages. The two-way communication device supports a Telocator Data Protocol by the Personal Communications Association for forwarding binary data to mobile computers. The standard facilitates transmission of images and faxes over paging and narrowband PCS networks. Alternatively, the two-way communication device 31 can be substituted with a cellular telephone.

[0219] The two-way communication device 31 has a receiver, a transmitter, and a switch, all are controlled by the CPU 20 via the bus of the handheld computer system of FIG. 1. The switch receives an input from the antenna 32 and appropriately routes the radio signal from the transmitter to the antenna 32, or alternatively, the radio signal from the antenna 32 to the

receiver in the event the processor 20 is expecting a message. Via the bus 26, the processor 20 controls the receiver, the transmitter, and the switch to coordinate the transmission and receipt of data packets. The receiver and transmitter are standard two-way paging devices or standard handheld cellular communication chips available from Motorola, Inc. in Schaumburg, Ill. or Philips Semiconductors in Sunnyvale, Calif. The antenna 32 is preferably a loop antenna using flat-strip conductors such as printed circuit board wiring traces as flat strip conductors have lower skin effect loss in the rectangular conductor than that of antennas with round-wire conductors.

[0220] The processor 20 of the preferred embodiment accepts handwritings as an input medium from the user. A digitizer 34, a pen 33, and a display LCD panel 35 are provided to capture the handwriting. Preferably, the digitizer 34 has a character input region and a numeral input region which are adapted to capture the user's handwritings on words and numbers, respectively. The LCD panel 35 has a viewing screen exposed along one of the planar sides of the enclosure are provided. The assembly combination of the digitizer 34, the pen 33 and the LCD panel 35 serves as an input/output device. When operating as an output device, the screen 35 displays computer-generated images developed by the CPU 20. The LCD panel 35 also provides visual feedback to the user when one or more application software execute. When operating as an input device, the digitizer 34 senses the position of the tip of the stylus or pen 33 on the viewing screen 35 and provides this information to the computer's processor 20. In addition to the vector information, the present invention contemplates that display assemblies capable of sensing the pressure of the stylus on the screen can be used to provide further information to the CPU 20.

[0221] The preferred embodiment accepts pen strokes from the user using the stylus or pen 33 which is positioned over the digitizer 34. As the user "writes," the position of the pen 33 is sensed by the digitizer 34 via an electromagnetic field as the user writes information to the data management computer system. The digitizer 34 converts the position information to graphic data that are transferred to a graphic processing software of the data logger computer system. The data entry/display assembly of pen-based computer systems permits the user to operate the data logging computer system as an electronic notepad. For example, graphical images can be input into the pen-based computer by merely moving the stylus over the surface of the screen. As the CPU 20 senses the position and movement of the stylus, it generates a corresponding image on the screen to create the illusion that the pen or stylus is drawing the image directly upon the screen. The data on the position and movement of the stylus is also provided to a handwriting recognition software, which is stored in the ROM 21 and/or the RAM 22. The handwriting recognizer suitably converts the written instructions from the user into text data suitable for saving time and expense information. The process of converting the pen strokes into equivalent characters and/or drawing vectors using the handwriting recognizer is described below.

[0222] Preferably, the handwriting recognizer of the present invention recognizes non-cursive characters in a fixed style using a basic character set, preferably a 36-character alphanumeric character set. In addition to the basic 26 letters and 10 digits, the non-cursive handwriting recognizer includes multi-step pen strokes that can be used for punctuation, diacritical marks, and capitalization. Preferably, the non-cursive handwriting recognizer is a software module called GRAFFITI, commercially available from Palm

Computing,  
Inc. Each letter in the non-cursive alphabet is a streamlined  
version of the  
standard block character--the letter A, for example, looks like a  
pointy  
croquet hoop, and the hoop must be started at the dot indicator at  
the lower  
right corner-- as illustrated and discussed in more detail in the  
above  
incorporated-by-reference U.S. patent applications. By restricting  
the way  
the user writes, the non-cursive handwriting recognizer achieves a  
more perfect  
recognition and, as with stenography, supports an alphabet consisting  
of  
characters that can be written much more quickly than conventional  
ones.

[0223] The computer system is also connected to one or more  
input/output (I/O)  
ports 42 which allows the CPU 20 to communicate with other computers.  
Each of  
the I/O ports 42 may be a parallel port, a serial port, or  
alternatively a  
proprietary port to enable the computer system to dock with the host  
computer.  
In the event that the I/O port 42 is housed in a docking port 84,  
after  
docking, the I/O ports 42 and software located on a host computer 82  
support an  
automatic synchronization of data between the computer system and the  
host  
computer. During operation, the synchronization software runs in the  
background mode on the host computer 82 and listens for a  
synchronization  
request or command from the computer system 10 of the present  
invention.  
Changes made on the computer system and the host computer will be  
reflected on  
both systems after synchronization. Preferably, the synchronization  
software  
only synchronizes the portions of the files that have been modified  
to reduce  
the updating times.

[0224] The I/O port 42 is preferably a high speed serial port such as  
an RS-232  
port, a Universal Serial Bus, or a Fibre Channel for cost reasons,  
but can also  
be a parallel port for higher data transfer rate. Preferably, the

I/O port 42 has a housing which is adapted to snappably connect to the housing of a Musical Instrument Digital Interface (MIDI) player 37, a fax modem 40, a voice recorder 43, a GPS receiver 46 and a barcode reader 48. When the I/O port 42 is connects to the MIDI player 37, the computer system 10 drives high quality audio speakers 38 and 39 which connect to the MIDI player 37 to support multimedia applications on the computer 10.

[0225] Additionally, via the serial port 42, a fax-modem 40 is adapted to receive information over a telephone 41 via a plain old telephone system (POTS) landline or over the radio frequencies and allow the user to access information untethered. Further, the modem 40 may serve as part of a wide-area-network to allow the user to access additional information. The fax-modem 40 can receive drawings and text annotations from the user and send the information over a transmission medium such as the telephone network or the wireless network to transmit the drawings/text to another modem or facsimile receiver, allowing the user to transmit information to the remote site on demand. The fax-modem 40 can be implemented in hardware or in software with a few additional components such as a DAA, as is known in the art.

[0226] The case is a rectangular plastic casing with a major opening on the top of the case to receive the LCD panel 35 and the digitizer 34. The case has a receptacle which is adapted to receive and store the pen 33. Furthermore, a plurality of push-buttons in the keypad 24 are positioned on the top side of the case. The push-buttons of the keypad 24 preferably allows the user to invoke one or more pre-installed software on the handheld computer. Additionally, the case has an opening on the backside which is adapted to receive a connector carrying the electrical impulses to and from the I/O port



42.

[0227] The handheld computer executes software stored in an executable format such as a prc file. The software allows the handheld computer to track Daily Field Journals, such as:

[0228] Work Progress of Unit Bid Items and Contract Deliverables

[0229] Manpower Utilization

[0230] Equipment Utilization

[0231] General Information including weather, temperature, remarks, and inspector's name.

[0232] The software also tracks an Inspection Checklist, such as:

[0233] Generation of Punch list items

[0234] Tracking of Punch list items

[0235] Facility Inventory

[0236] Facility Repairs & Cost Estimates

[0237] The software also keeps Project Documentation and captures, among others:

[0238] Project Specifications

[0239] Industry Specifications

[0240] Drawing Logs

[0241] FIG. 10 shows an exemplary process 500 for collecting data in the field and uploading the data to the computer of FIG. 1. First, a user collects work in progress data (step 510). The information collected includes project/contract identification, inspector identification, item number, location, and one or more description of activities. Various exemplary screens on a handheld computer for step 510 are shown as FIGS. 11-18. Next, the user collects labor related cost (step 520). The information collected in

step 520  
includes labor type, quantity and hours. Next, the process 500  
collects  
equipment being used for the project (step 530). The information  
collected  
includes equipment type, quantity, hours in use and stand-by hours.  
Next, the  
process 500 collects additional submittal information (step 540).  
The  
information collected includes weather condition, comments, and the  
name of the  
inspector, among others. The process 500 then sends the collected  
information  
to the system of FIG. 1 (step 550). This can be done wirelessly  
using a  
wireless handheld unit such as the Palm VII, available from Palm  
Computing.  
Alternatively, the information can be transmitted using a modem or  
using an  
external computer with a suitable hot-sync cradle. In the later  
case, the  
handheld unit is synchronized with the external computer and, upon  
concluding  
the synchronization, the external computer opens a connection with  
the server  
of FIG. 1 and transmits the collected data from the handheld unit.  
The  
collected information is then imported to the database of FIG. 1, and  
appropriate data import operations and report generation operations  
can be done  
(step 560). The process 500 then exits.

[0242] After collecting data, the handheld computer is placed in a  
hot sync  
cradle or aligned with an infrared port on a host computer for data  
transfer.  
The user, or inspector, activates a data receiving software on a  
workstation or  
a laptop. The user selects an icon to initiate data uploads and  
downloads to  
the handheld computer. The user will select the project to be  
updated or  
refreshed before selecting the icon. Only changed project  
information will be  
uploaded. The downloading of project information is performed the  
same way, a  
project is selected and selection of the icon initiates the file  
transfer. The  
file transfer results in the project information stored in a database  
to be

converted to a handheld format such as a "pdb format". The "pdb format" will result in an individual project table to be generated for each project on the handheld computer. Updates to the table is done in the same manner as described above.

[0243] FIG. 19 shows an exemplary process 600 to handle quality assurance to check one or more construction projects. The process 600 provides an interface for efficient operation and expedient problem resolution. First, a service request is generated (step 602). Based on the service request, a work order is generated (step 604). The work order is entered (step 606), and various forms such as daily project forms are filled with data (step 608).

[0244] Data collected includes work performed by subcontractors, and materials produced by fabricators, suppliers and vendors. The process also monitors the process control program to assure it is functioning and supports acceptance inspections and acceptance sampling and testing. Data collected can also include material data on Cement; Reinforcing Steel Epoxy; Reinforcing Steel; Precast, Prestressed Concrete Structures; Ready-Mix Concrete; Fly Ash and Pozzolan; Asphalt Emulsion; Asphalt Binder; Hydrated Lime; and Concrete Pumping. Further, the system collects acceptance testing data on manufactured materials such as aggregates, Hot Asphalt Mixes, and Portland Cement Concrete products. For other commercially fabricated materials, the system collects data on the Manufacturer's Certificate of Compliance.

[0245] Using a suitable field computer such as the handheld computer described above, the quality personnel performs full time surveillance during construction. In addition to daily inspection of the physical performance of the work, surveillance may include any combination of the following:

[0246] a) Observation of Process Control measures performed;

[0247] b) Review or spot checks of procedures or instructions governing the work, including inspection and test procedures;

[0248] c) Evaluation or verification of the presence and effectiveness of Project controls;

[0249] c) Discussion with personnel performing or supervising the work.

[0250] The results of the surveillance are documented in the Daily Inspection Report and reported to a Segment Quality Engineer responsible for the activity

[0251] Completed items can be inspected for completeness, markings, calibration, adjustments, protection from damage, or other characteristics required to verify the quality of workmanship and conformance of the item to specified requirements

[0252] Quality records can be examined for adequacy and completeness and available for audit.

[0253] Inspection and test results can be documented in accordance with the quality plan.

[0254] Prior to final inspections and tests, a review of the deficiencies identified during the acceptance inspections and tests can be performed to verify that corrective action has been completed, verified and documented. The final inspection or test can demonstrate the conformance of the item to specified requirements.

[0255] After each daily data collection by quality field personnel, the data on the handheld device is uploaded to the handheld device using a process known as hot-syncing (step 610). When new data has been uploaded, the project manager is notified (step 612). The manager reviews the daily project data collected

using the handheld device (step 614) and generates daily project reports (step 616). Additionally, a key indicator summary report is generated from consolidated daily project reports (step 618). The summary report and/or the daily project reports are posted on a web site (step 620).

[0256] The customer is notified after reports have been posted on the web site (step 622). The user can then go on-line and select a project specific web site using a browser, for example (step 624). Upon entering the project specific web site, the user enters his or her identification and password (step 626) and proceeds to view the daily project reports as well as the key indicator summary reports (step 628). Construction progress is updated monthly, by the status of the summaries. The process also provides daily acceptance information by work activity, consistent with the work schedule. The quality testing and acceptance data are identified by the same activity numbering system used in the construction schedule and invoicing process. Identifying work activities consistently between the work schedule, payment schedule and quality testing and inspection reports assures fair and reasonable progressing of the work. Work documented as deficient, or work not being performed in accordance with the contract is identified by the system for follow-up if necessary.

[0257] During use, the user provides various "released for construction" plans that have been through the quality review process to a builder and a work plan is developed. The builder performs the work by following good construction practices and process control procedures. A combination of process inspections, testing and surveillance is performed using the process 600 in a systematic manner to assure the specific requirements for control of the process and quality of the item are being achieved throughout the duration of

the process. Inspection and testing of items in process or under construction is performed for work activities as required in the quality plan to verify conformance to the requirements. Process control inspections and tests may be performed by the Process Control group, and inspections and tests include qualification tests, factory tests, installation and verification tests, material tests and pre-operational checks/tests. The source inspection of items fabricated or manufactured specifically for the Project will be performed jointly as required by the Contract Documents. Items furnished by suppliers to be incorporated into the Work, such as commercial items, bulk materials, subassemblies, and subcontractor/supplier furnished items, can be inspected upon receipt. Inspection/testing activities for purposes of acceptance shall be independent from those used for process control. Individuals performing the inspections/testing can be qualified and certified as necessary to perform the applicable task. The customer can review on-line to see if the process control processes have been followed as detailed in the quality plan. When an element of work has progressed to a point that it would be covered by the next element and would not be easily inspected or accessible, the builder can request an acceptance inspection. This would occur when the builder deems the work progress; including process control; has been completed and is ready for acceptance inspection and testing. Acceptance Inspections and Tests can be performed, and the results are evaluated to verify acceptability and conformance to the contract requirements. Acceptance will be based on conforming results. The process 600 supports inspection checks that include the following:

[0258] Identification of the individuals or groups responsible for performing the inspection or test, including material testing laboratory;

[0259] Items to be inspected;

[0260] Location of inspection/test (on/off site);

[0261] Identification of characteristics and activities to be inspected or tested;

[0262] A description of the method of inspection or test;

[0263] Acceptance criteria;

[0264] Identification of procedures, drawings and specifications;

[0265] Frequency of the required inspections or tests

[0266] The process 600 supports a three (3)-phase inspection plan:

[0267] Phase 1--Preparatory Inspection Review

[0268] Prior to the start of work on an identified feature of work, the user will review and become familiar with the released for construction plans. They will participate in the pre-activity meetings. They will understand the quality procedures, work plan and the requirements of the Contract Documents. The purpose of the pre-activity meeting is to assure there is no misunderstanding as regards to the quality, as well as safety and environmental issues, material and equipment contemplated, testing requirements, acceptance criteria, including workmanship and documentation to be submitted attesting the achievement of the quality and technical requirements

[0269] Phase 2--Daily Inspection Reviews (Surveillance)

[0270] The quality Field Inspectors will review and monitor the work on the Project on a daily basis using the process 600. They can communicate to the customer any perceived conditions that could result in rework.

[0271] Phase 3--Acceptance Inspection and Testing

[0272] When an item of work has been completed and is ready for acceptance

inspection and testing the customer will request quality personnel to perform the acceptance inspection and testing. The quality personnel then performs the testing, the conforming results of the testing and an acceptable inspection will constitute acceptance of the work element being considered for acceptance. When acceptance is not achieved a corrective actions for the noted deficiency will be identified prior to the start of the next operation. This inspection does not constitute final acceptance. Deficiencies noted during the inspections will be identified and documented so a follow-up inspection can be performed. Work that has not been accepted cannot be progressed for payment.

[0273] Although the invention has been described with reference to specific embodiments, this description is not to be construed in a limiting sense. Various modifications of the disclosed embodiments, as well as alternative embodiments, will be apparent to persons skilled in the art. It is, therefore, contemplated that the appended claims will cover all modifications that fall within the true scope of the invention.

#### CLAIMS:

What is claimed is:

1. A construction management system, comprising: a handheld computer adapted to collect construction quality data from the field; a planning system to track budgetary information; a design system to perform site engineering assessment; and a construction system to track material consumption and progress for each project, the construction system adapted to receive quality data collected from the handheld computer, store daily project reports and generate key indicator reports.
2. The system of claim 1, wherein the handheld computer collects



work in  
progress data.

3. The system of claim 1, wherein the handheld computer collects project and contract identification, inspector identification, item number, location, and one or more description of activities.

4. The system of claim 1, wherein the handheld computer collects labor related information.

5. The system of claim 1, wherein the handheld computer collects labor type, quantity and hours.

6. The system of claim 1, wherein the handheld computer collects equipment information.

7. The system of claim 1, wherein the handheld computer collects equipment type, quantity, hours in use and stand-by hours.

8. The system of claim 1, wherein the handheld computer collects submittal information.

9. The system of claim 1, wherein the handheld computer collects weather condition, comments, and an inspector name.

10. The system of claim 1, wherein the handheld computer hot-syncs collected information to a server.

11. The system of claim 10, wherein the collected information is hot-synced wirelessly using a wireless handheld unit.

12. The system of claim 10, further comprising a modem coupled to the handheld computer, wherein the information can be hot-synced using a modem.

13. The system of claim 10, further comprising a hot-sync cradle coupleable to the handheld computer, the cradle hot-syncing the collected information for transmission to a server.

14. A method for managing a construction project, comprising:  
collecting  
construction data from the field with a handheld computer; tracking  
budgetary  
information using a planning system; performing site engineering  
assessment  
using a design system; and tracking material consumption and  
progress for each  
project using a construction system, the construction system adapted  
to receive  
data collected from the handheld computer, store daily project  
reports and  
generate key indicator reports.

15. The method of claim 14, further comprising collecting work in  
progress  
data using the handheld computer.

16. The method of claim 14, further comprising collecting labor  
related  
information using the handheld computer.

17. The method of claim 14, further comprising collecting equipment  
information using the handheld computer.

18. The method of claim 14, further comprising collecting submittal  
information using the handheld computer.

19. The method of claim 14, wherein the handheld computer collects  
project and  
contract identification, inspector identification, item number,  
location, one  
or more description of activities, labor type, quantity, hours,  
weather  
condition, comments, and an inspector name.

20. The method of claim 14, further comprising hot-syncing collected  
information to server over land-line or wireless medium.

21. The method of claim 14, further comprising collecting field  
testing  
information using the handheld computer.

22. The method of claim 14, further comprising collecting quality  
assurance  
testing information using the handheld computer.